# The Rehabilitation of Ontario's Kam Kotia Mine

#### **Presented by: Richard Bradley**

SOUTH UNIMPOUNDED TAILINGS

> KAM KOTIA PLANT SITE

> > ACCESS ROAD

## Background

- Kam Kotia is a former Cu/Zn mine near Timmins, Ontario
- There are about 6 million tonnes of acid generating tailings, originally covering more than 500 ha
- Environmental impacts are locally significant
  - acidic leachate, high metal levels
  - dusting
  - aesthetics
  - physical safety

## MINE HISTORY

Principle exploration 1926-1928, exploration shaft
Mining \* 1943-1944 - 169,000 tonnes open pit
Mining 1961-1972 - 5,840,000 tonnes, mainly underground
Production 6.6 MT @ 1.1% Cu, 1.17% Zn, 0.10 oz/Ag

Site became the responsibility of the Crown in 1988

NORTH IMPOUNDED TAILINGS (NJT)

SOUTH UNIMPOUNDED TAILINGS (SUT)

HIGHWAY 576

KAM KOTIA PLANT SITE NORTH UNIMPOUNDED TAILINGS (NUT)

100.00


ACCESS ROAD





## HYDROLOGY

- North and East seeps drain NUT, E1/2 of NIT and N1/2 plant site ⇒ Kamiskotia River
- South seep drains SUT, S1/ of NIT and plant site to Little Kamiskotia River ⇒ Kamiskotia River



1000m


FIGURE 2.5-6





#### BACKGROUND

- The total rehabilitation of the abandoned Kam Kotia Mine site is to be conducted as a proposed five-phase program.
- This rehabilitation plan was developed during fiscal 2000/01, and predicted a total rehabilitation cost of more than \$41 million.
  - The cost <u>estimates</u> were as follows, including a 30% contingency:
    - Phase "A": \$4.985 million
    - Phase "B": \$3.285 million
    - Phase "C": \$8.190 million
    - Phase "D": \$3.372 million
    - Phase "E": \$11.766 million
    - Effluent treatment for 50 years: \$9.698 million



#### BACKGROUND

Phase A: Treatment plant with collection system; NUT impoundment.
Phase B: SUT tails into NUT impoundment.
Phase C: NUT tails into NUT impoundment.
Phase D: cap NUT impoundment.
Phase E: NIT cover.

#### PHASE "A"

- Phase "A" involved the construction of a Lime Addition Treatment Plant, as well as all of its required infrastructure, and the construction of a new NUT impoundment dam structure.
  - The combined cost of these Phase "A" bids was \$9.85 million, and the work was completed by July 2002.
- Realized that the combined costs of Phases "A" and "B" would approach \$14 million.











#### PHASE "B"

 Phase "B" involved the relocation of the SUT tailings to within the new NUT impoundment area.

Upon completion of the work, more than 340,000 m<sup>3</sup> of SUT tailings had been relocated and buffered with Envirolime, at a cost of \$3.4 million.

Phase "B" work was completed by mid-March 2003.





#### PHASE "C"

Phase "C" involved the relocation of the NUT tailings to within the new NUT impoundment area.

Upon completion of the work, more than 611,000 m<sup>3</sup> of NUT tailings had been relocated and buffered with Envirolime, at a cost of \$6.9 million.

The Phase "C" work was completed by late-March, 2004.

## However.....

#### .... in abandoned mine rehabilitation, like any construction project, ....

# Things don't always go exactly as planned!

NORTH IMPOUNDED TAILINGS

INTERCEPTION DITCH

HIGHNAN 576

LIME PLANT

NEW NUT IMPOUNDMENT AREA

FORMER SOUTH UNIMPOUNDED TAILINGS

MINE SITE A

NORTH UNIMPOUNDED TAILINGS

ACCESS ROAD

#### **NUT Water Quality, October, 2003**

Parameter	Units	Result
pH		2.58
Acidity	mg/Las CaCO3	3980
A	mg/L	104
As	mg/L	0.08
Co	mg/L	3.87
Cu	mg/L	25.5
Fe	mg/L	1320
Zn	mg/L	188

- Timmins received two years of anomalously high precipitation.
  - The NUT Impoundment Area filled with approximately 600,000 m3 of water at a pH of about 2.7, and containing very high acidity and metals.
- In order not to delay the project, a decision was made to stack the NUT tailings in the impoundment area during Phase "C".

- Efforts were made to conduct the "in-situ" treatment of the NUT "Pond" during the winter of 2003/04.
- 706 tonnes of lime were added to the Pond, followed by over 2,000 tonnes of caustic (e.g. NaOH).
- Managed to raise the pH sufficiently to allow the discharge of the contaminated water for ~ 3 hours.
- Eventually ceased the treatment after having spent \$1.8 million.









- Efforts to neutralize the NUT ceased in the spring of 2004.
- By this time the NUT tails had been stacked within the NUT impoundment, but not leveled as planned.
- A consultant was hired to recommend how the NUT could best be emptied.

 Recommended a method involving neutralization with caustic and subsequent filtration using geotextile bags. NORTH IMPOUNDED TAILINGS

Contra Carter

LIME PLANT

FORMER SOUTH UNIMPOUNDED TAILINGS MINE

FORMER NORTH UNIMPOUNDED TAILINGS

- A contract was awarded in the spring of 2005 to conduct the treatment and discharge of the contaminated NUT water and to place the stacked NUT tailings into their proper location.
- The work was completed on schedule: the NUT emptied in the fall of 2005, and the tailings in NUT leveled by the spring of 2006.
- The final cost of this contract was \$9.4 million.



13/09/2005



















## NIT Area Cover

• The NIT area "dry" cover was to have been built as part of Phase "E".

In order for the KKM rehabilitation work to continue, the first two layers of that cover were constructed during the winter of 2004/05, at a cost of \$3.4 million.







#### **Rehabilitation Yet To Be Done ...**

- Complete the NIT cover (GCL, clay, granular B, soil, reveg) – this work is expected to cost more than \$10 million, so it will have to be conducted during two separate fiscal years.
  - Collect the remainder of the unimpounded tailings.
- Conduct Phase "D", which involves the construction of the "moist" cover over the NUT impoundment area.
- Conduct the remainder of Phase "E", which will include the rehabilitation of the open pit and all of the physical hazards on the site, such as the shaft and the thin crown pillar.

#### Recommendations

 Diversify funding- The OMA partnered with MNDM on the revegetation of the NUT impoundment dams. Contingency- Build a "contingency" allowance into your bids so that you can deal with the unforeseen - a 50% cost increase is not unusual.

### **Recommendations** (cont'd)

- Be flexible- stacking of the tailings, pumping water from the bags, discharge location.
- Watch the weather- can have a major impact on your project.
- Don't be discouraged- unforeseen things WILL happen.

#### The final cost for the rehabilitation of the Kam Kotia Mine site is now expected to be in the range of.....

# \$55 million