

## **Mine Tailings Water Treatment**

September 11st, 2018

Wayne Ingham, Ph.D.

**BluMetric Environmental Inc.** 

#### **Overview**

#### **TUNDRA MINE CHALLENGE**

Logistics and Schedule

#### **DESIGN REQUIREMENTS**

- Logistical Constraints
- Treatment Requirements
- Construction Requirements
- Analytical Requirements



# Tundra Mine Tailings Water Treatment



# Tundra Mine Tailings Water Treatment





### **Tundra Mine Challenge**

- Very short timeframe
- Remote location
- No roads
- High quality of treatment required
- Large volume to be treated
- Need to train for staffing
- Must disassemble and remove



#### **2009 Pilot - Timeframe**

- Bid in mid-May
- Award on June 15<sup>th</sup>
- Equipment to Yellowknife on July 6<sup>th</sup>
- Onsite by July12<sup>th</sup>
- Construction complete and ready to discharge July 19<sup>th</sup>
- First discharge on July 29<sup>th</sup>
- Reached design volume of 120,000 m<sup>3</sup> Sept 7<sup>th</sup>
- Ceased treating Sept 24<sup>th</sup> at 180,000 m<sup>3</sup>



# **Traditional Set-up**



# **Transport Constraints**



## **The Design Needs**

- Air access
- Small components
- Rapid delivery
- Ease of construction
- Building block design
- Treat 24/7
- Direct discharge



#### **Variables**

- Flow Volumes
- Concentrations
- New Contaminants of Concern
- Extremely High TSS
  - Low tailings pond
  - Weather



### **Configurable Treatment Trains**

- Flexibility in treatment train configuration
- Series for double pass and pH manipulation
- Parallel when appropriate and able to achieve higher flows








#### **Chemical Treatment Process**

- Precipitating arsenic from solution
- Chemical reaction with ferric sulphate (ferric) and lime
- Minimum ratio of iron to arsenic (by weight) of 5:1
- Arsenic, zinc and other heavy metals are precipitated as metal hydroxide and adsorb to create flocs.
- Polishing treatment of zinc and lead
- Degraded influent quality
- Injection of a SMB to precipitate metal sulphides
- Solids separated by dewatering using Geotubes®
- Discharge to the environment



# **Plant Design and Layout**



### **Treatment Quality**

#### **ARSENIC LEVELS**

- Influent levels around 3 ppm
- Required a maximum of .5 ppm
- Finite chemicals on site
- Positive capture of the contaminant
- Require immediate and direct discharge






# Discharge & Contract Criteria

Parameter		Effluent Criteria		
	Unit	Contract Specifications: Maximum Daily Average Concentration	Water License Criteria: Monthly Average Concentration	Water Licence Criteria: Maximum Concentration of Any Grab Sample
Metals				
Total arsenic	mg/L	0.20	0.50	1.00
Total copper	mg/L	0.01	0.01	0.02
Total lead	mg/L	0.01	0.01	0.02
Total nickel	mg/L	0.05	0.05	0.10
Total zinc	mg/L	0.02	0.02	0.04
Anions				
Nitrate (as N)	mg/L	5.00	5.00	10.0
Nitrite (as N)	mg/L	0.40	0.40	0.80
Conventional Parameters				
Total ammonia nitrogen	mg/L	5.00	5.00	10.0
Total suspended solids	mg/L	15.0	15.0	30.0
рН	-	6 - 9	6-9	6 - 9

# **Structural Components**



### **Assembled Plant**



#### **Solids**

- Hyroxide precipitation design to trap arsenic in a metal flock
- Must capture the flock for treatment to be effective
- Had to do that in positive and immediate way
- Must be able to handle new design flows of 150 m<sup>3</sup>/hr from 60 m<sup>3</sup>/hr
- Had to operate 24/7 with minimum attention





### **Inflated Geotube**




### **Onsite Laboratory**

- AA allowing for low level zinc and arsenic detection
- Allowed much greater control of the treatment process and real time adaptation to changes to influent chemistry

Ensured plant maintained discharge compliance at all

times






# **Onsite Laboratory**









#### Results





#### **Results**



#### Results







#### **Final Benefits**

- 180,000 m<sup>3</sup> of tailings water treated to an average of .08 ppm arsenic
- Over 58 days w/ average operation time 23 hr/d
- Average solids in discharge of 5 ppm
- Water levels reduced by 0.4 meters below requirement
- Lower pond final level 7.65
- Local community members trained as operators
- Over 80% of project was aboriginal labour
- Completed on time spec and on budget



### **Treatment Progress**

- 2009 Dual Train Pilot: 180,000 m<sup>3</sup>
- 2010 Dual Train: 250,000 m<sup>3</sup>
- 2011 Triple Train: 300,000 m<sup>3</sup>
- 2012 Dual Train (Not onsite): 350,000 m<sup>3</sup>
- 2013-2016 Dual Train: 100,000 m<sup>3</sup> 200,000 m<sup>3</sup>
- 2017 Dual Train (New): 60,000 m<sup>3</sup>
- 2018 (No Treatment Required)
- Total: ~1.8 million m<sup>3</sup>





### **Overview**















#### **Site Closure**



# **Long Term Monitoring**



# **Remote Monitoring**



